

Name of work: **Digging of Pond and construction of bamboo made Retaining Wall (Pond No.1) at Cocotilla Farm**

Division: **Main Scheme**

Location: **ICAR Research Complex, Lembucherra**

Rate: **Tripura Schedule of Rates 2008 for Buildings**

<b>Item No. &amp; details of work to be executed</b>		<b>Rate</b>	<b>Amount</b>	
<b>Description</b>	<b>Quantity</b>		<b>In figure</b>	<b>In words</b>
<b>Item No.1:</b> Providing and fixing barak bamboo, 75mm to 100mm dia posts, runners struts, bracing collars etc. fixed with MS nails, complete as per specification at Page 136, item 21.19 of TSR 2008: 110m L x 12m W x 4.9m H	6468 cum			
<b>Item No.2:</b> Providing and fixing muli bamboo champa-kampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both sides) at 300mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification at page 135, item 21.9 of TSR 2008: 110m L x 2.8m W	308.00 sqm			
<b>Item No.3:</b> Clearing of jungle i/c uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth up to 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish up to a distance of 50m outside the periphery of the area cleared as CPWD specification (Page 7, item 2.14): 110m L x 1.8m W	198.00 sqm			
<b>Item No.4:</b> Pumping out water bodies like ponds, lakes as per CPWDF specification (Page 8, item 2.17): 35m L x 20m W x 1.5m H	1050.00 cum			
<b>Item No.5:</b> Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30cm, 1.5m in width as well as 10 sqm on plan) i/c disposal of excavated earth lead up to 50m outside the periphery of the area and neatly dressed as per CPWD classification (page 5, item 2.1): 35m L x 20m W x 1.5m H	1050.00 cum			

Contd....2

Total A (Items 1 to5)				
B. Add overheads for site accommodation, mobilization/demobilization of resources, labour camps with minimum amenities required as labour laws etc. .....% of A				
C. Add cost index.....% of A				
Grand total (A+B+C)				
Grand Total rounded off				

Quoted cost: Rs..... (Rupees.....  
.....) only

Date:.....

Signature with seal

List of enclosures:

1. Deposit-at-Call for Rs..... (Rupees ..... ) only  
No..... of .....(Bank), ..... Branch.
2. Copy of ITC, PTC, Labour registration
3. Copy of PWD/CPWD/MES/BSNL enlistment
4. ....

भाकृ अनुप - पूषप  
ICAR-RC-NEH

Name of work: **Digging of Pond and construction of bamboo made Retaining Wall (Pond No.2) at Cocotilla Farm**

Division: **Main Scheme**

Location: **ICAR Research Complex, Lembucherra**

Rate: **Tripura Schedule of Rates 2008 for Buildings**

<b>Item No. &amp; details of work to be executed</b>		<b>Rate</b>	<b>Amount</b>	
<b>Description</b>	<b>Quantity</b>		<b>In figure</b>	<b>In words</b>
<b>Item No.1:</b> Providing and fixing barak bamboo, 75mm to 100mm dia posts, runners struts, bracing collars etc. fixed with MS nails, complete as per specification at Page 136, item 21.19 of TSR 2008: 62m L x 12m W x 4.9m H	3645.60 cum			
<b>Item No.2:</b> Providing and fixing muli bamboo champa-kampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both sides) at 300mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification at page 135, item 21.9 of TSR 2008: 62m L x 2.8m W	173.50 sqm			
<b>Item No.3:</b> Clearing of jungle i/c uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth up to 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish up to a distance of 50m outside the periphery of the area cleared as CPWD specification (Page 7, item 2.14): 62m L x 1.8m W	111.60 sqm			
<b>Item No.4:</b> Pumping out water bodies like ponds, lakes as per CPWDF specification (Page 8, item 2.17): 20m L x 11m W x 1.5m H	330.00 cum			
<b>Item No.5:</b> Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30cm, 1.5m in width as well as 10 sqm on plan) i/c disposal of excavated earth lead up to 50m outside the periphery of the area and neatly dressed as per CPWD classification (page 5, item 2.1): 20m L x 11m W x 1.5m H	330.00 cum			

Contd....2

Total A (Items 1 to5)				
B. Add overheads for site accommodation, mobilization/demobilization of resources, labour camps with minimum amenities required as labour laws etc. .....% of A				
C. Add cost index.....% of A				
Grand total (A+B+C)				
Grand Total rounded off				

Quoted cost: Rs..... (Rupees.....  
.....) only

Date:.....

Signature with seal

List of enclosures:

1. Deposit-at-Call for Rs..... (Rupees ..... ) only  
No..... of .....(Bank), ..... Branch.
2. Copy of ITC, PTC, Labour registration
3. Copy of PWD/CPWD/MES/BSNL enlistment
4. ....

भाकृ अनुप - पूषप  
ICAR-RC-NEH

Name of work: **Digging of Pond and construction of bamboo made Retaining Wall (Pond No.3) at Cocotilla Farm**

Division: **Main Scheme**

Location: **ICAR Research Complex, Lembucherra**

Rate: **Tripura Schedule of Rates 2008 for Buildings**

<b>Item No. &amp; details of work to be executed</b>		<b>Rate</b>	<b>Amount</b>	
<b>Description</b>	<b>Quantity</b>		<b>In figure</b>	<b>In words</b>
<b>Item No.1:</b> Providing and fixing barak bamboo, 75mm to 100mm dia posts, runners struts, bracing collars etc. fixed with MS nails, complete as per specification at Page 136, item 21.19 of TSR 2008: 68m L x 12m W x 4.9m H	3998.40 cum			
<b>Item No.2:</b> Providing and fixing muli bamboo champa-kampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both sides) at 300mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification at page 135, item 21.9 of TSR 2008: 68m L x 2.8m W	190.40 sqm			
<b>Item No.3:</b> Clearing of jungle i/c uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth up to 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish up to a distance of 50m outside the periphery of the area cleared as CPWD specification (Page 7, item 2.14): 68m L x 1.8m W	122.40 sqm			
<b>Item No.4:</b> Pumping out water bodies like ponds, lakes as per CPWDF specification (Page 8, item 2.17): 23m L x 11m W x 1.5m H	379.50 cum			
<b>Item No.5:</b> Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30cm, 1.5m in width as well as 10 sqm on plan) i/c disposal of excavated earth lead up to 50m outside the periphery of the area and neatly dressed as per CPWD classification (page 5, item 2.1): 35mL x 20mW x 1.5mH	379.50 cum			

Contd....2

Total A (Items 1 to5)				
B. Add overheads for site accommodation, mobilization/demobilization of resources, labour camps with minimum amenities required as labour laws etc. .....% of A				
C. Add cost index.....% of A				
Grand total (A+B+C)				
Grand Total rounded off				

Quoted cost: Rs..... (Rupees.....  
.....) only

Date:.....

Signature with seal

List of enclosures:

1. Deposit-at-Call for Rs..... (Rupees ..... ) only  
No..... of .....(Bank), ..... Branch.
2. Copy of ITC, PTC, Labour registration
3. Copy of PWD/CPWD/MES/BSNL enlistment
4. ....

भाकृ अनुप - पूषप  
ICAR-RC-NEH

Name of work: **Digging of Pond and construction of bamboo made Retaining Wall (Pond No.4) at Cocotilla Farm**

Division: **Main Scheme**

Location: **ICAR Research Complex, Lembucherra**

Rate: **Tripura Schedule of Rates 2008 for Buildings**

<b>Item No. &amp; details of work to be executed</b>		<b>Rate</b>	<b>Amount</b>	
<b>Description</b>	<b>Quantity</b>		<b>In figure</b>	<b>In words</b>
<b>Item No.1:</b> Providing and fixing barak bamboo, 75mm to 100mm dia posts, runners struts, bracing collars etc. fixed with MS nails, complete as per specification at Page 136, item 21.19 of TSR 2008: 68m L x 12m W x 4.9m H	3998.40 cum			
<b>Item No.2:</b> Providing and fixing muli bamboo champa-kampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both sides) at 300mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification at page 135, item 21.9 of TSR 2008: 68m L x 2.8m W	190.40 sqm			
<b>Item No.3:</b> Clearing of jungle i/c uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth up to 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish up to a distance of 50m outside the periphery of the area cleared as CPWD specification (Page 7, item 2.14): 68m L x 1.8m W	122.40 sqm			
<b>Item No.4:</b> Pumping out water bodies like ponds, lakes as per CPWDF specification (Page 8, item 2.17): 23m L x 11m W x 1.5m H	379.50 cum			
<b>Item No.5:</b> Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30cm, 1.5m in width as well as 10 sqm on plan) i/c disposal of excavated earth lead up to 50m outside the periphery of the area and neatly dressed as per CPWD classification (page 5, item 2.1): 23m L x 11m W x 1.5m H	379.50 cum			

Contd....2

Total A (Items 1 to5)				
B. Add overheads for site accommodation, mobilization/demobilization of resources, labour camps with minimum amenities required as labour laws etc. .....% of A				
C. Add cost index.....% of A				
Grand total (A+B+C)				
Grand Total rounded off				

Quoted cost: Rs..... (Rupees.....  
.....) only

Date:.....

Signature with seal

List of enclosures:

1. Deposit-at-Call for Rs..... (Rupees ..... ) only  
No..... of .....(Bank), ..... Branch.
2. Copy of ITC, PTC, Labour registration
3. Copy of PWD/CPWD/MES/BSNL enlistment
4. ....

भाकृ अनुप - पूषप  
ICAR-RC-NEH



Name of work: **Digging of Pond and construction of bamboo made Retaining Wall (Pond No.5) at Cocotilla Farm**

Division: **Main Scheme**

Location: **ICAR Research Complex, Lembucherra**

Rate: **Tripura Schedule of Rates 2008 for Buildings**

<b>Item No. &amp; details of work to be executed</b>		<b>Rate</b>	<b>Amount</b>	
<b>Description</b>	<b>Quantity</b>		<b>In figure</b>	<b>In words</b>
<b>Item No.1:</b> Providing and fixing barak bamboo, 75mm to 100mm dia posts, runners struts, bracing collars etc. fixed with MS nails, complete as per specification at Page 136, item 21.19 of TSR 2008: 108m L x 12m W x 4.9m H	6350.40 cum			
<b>Item No.2:</b> Providing and fixing muli bamboo champa-kampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both sides) at 300mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification at page 135, item 21.9 of TSR 2008: 108m L x 2.8m W	302.00 sqm			
<b>Item No.3:</b> Clearing of jungle i/c uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth up to 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish up to a distance of 50m outside the periphery of the area cleared as CPWD specification (Page 7, item 2.14): 108m L x 1.8m W	194.40 sqm			
<b>Item No.4:</b> Pumping out water bodies like ponds, lakes as per CPWDF specification (Page 8, item 2.17): 37m L x 17m W x 1.5m H	943.50 cum			
<b>Item No.5:</b> Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30cm, 1.5m in width as well as 10 sqm on plan) i/c disposal of excavated earth lead up to 50m outside the periphery of the area and neatly dressed as per CPWD classification (page 5, item 2.1): 23m L x 11m W x 1.5m H	943.50 cum			

Contd....2

Total A (Items 1 to5)				
B. Add overheads for site accommodation, mobilization/demobilization of resources, labour camps with minimum amenities required as labour laws etc. .....% of A				
C. Add cost index.....% of A				
Grand total (A+B+C)				
Grand Total rounded off				

Quoted cost: Rs..... (Rupees.....  
.....) only

Date:.....

Signature with seal

List of enclosures:

1. Deposit-at-Call for Rs..... (Rupees ..... ) only  
No..... of .....(Bank), ..... Branch.
2. Copy of ITC, PTC, Labour registration
3. Copy of PWD/CPWD/MES/BSNL enlistment
4. ....

भाकृ अनुप - पूषप  
ICAR-RC-NEH

Name of work: **Digging of Pond and construction of bamboo made Retaining Wall (Pond No.6) at Cocotilla Farm**

Division: **Main Scheme**

Location: **ICAR Research Complex, Lembucherra**

Rate: **Tripura Schedule of Rates 2008 for Buildings**

<b>Item No. &amp; details of work to be executed</b>		<b>Rate</b>	<b>Amount</b>	
<b>Description</b>	<b>Quantity</b>		<b>In figure</b>	<b>In words</b>
<b>Item No.1:</b> Providing and fixing barak bamboo, 75mm to 100mm dia posts, runners struts, bracing collars etc. fixed with MS nails, complete as per specification at Page 136, item 21.19 of TSR 2008: 114m L x 12m W x 4.9m H	6703.20 cum			
<b>Item No.2:</b> Providing and fixing muli bamboo champa-kampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both sides) at 300mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification at page 135, item 21.9 of TSR 2008: 114 L x 2.8m W	319.20 sqm			
<b>Item No.3:</b> Clearing of jungle i/c uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth up to 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish up to a distance of 50m outside the periphery of the area cleared as CPWD specification (Page 7, item 2.14): 114m L x 1.8m W	205.20 sqm			
<b>Item No.4:</b> Pumping out water bodies like ponds, lakes as per CPWDF specification (Page 8, item 2.17): 37m L x 20m W x 1.5m H	1110.00 cum			
<b>Item No.5:</b> Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30cm, 1.5m in width as well as 10 sqm on plan) i/c disposal of excavated earth lead up to 50m outside the periphery of the area and neatly dressed as per CPWD classification (page 5, item 2.1): 23m L x 20m W x 1.5m H	1110.00 cum			

Contd....2

Total A (Items 1 to5)				
B. Add overheads for site accommodation, mobilization/demobilization of resources, labour camps with minimum amenities required as labour laws etc. .....% of A				
C. Add cost index.....% of A				
Grand total (A+B+C)				
Grand Total rounded off				

Quoted cost: Rs..... (Rupees.....  
.....) only

Date:.....

Signature with seal

List of enclosures:

1. Deposit-at-Call for Rs..... (Rupees ..... ) only  
No..... of .....(Bank), ..... Branch.
2. Copy of ITC, PTC, Labour registration
3. Copy of PWD/CPWD/MES/BSNL enlistment
4. ....

भाकृ अनुप - पूषप  
ICAR-RC-NEH

Name of work: **Digging of Pond and construction of bamboo made Retaining Wall [Pond No.7 (1)] at Cocotilla Farm**  
 Division: **Main Scheme**  
 Location: **ICAR Research Complex, Lembucherra**  
 Rate: **Tripura Schedule of Rates 2008 for Buildings**

<b>Item No. &amp; details of work to be executed</b>		<b>Rate</b>	<b>Amount</b>	
<b>Description</b>	<b>Quantity</b>		<b>In figure</b>	<b>In words</b>
<b>Item No.1:</b> Providing and fixing barak bamboo, 75mm to 100mm dia posts, runners struts, bracing collars etc. fixed with MS nails, complete as per specification at Page 136, item 21.19 of TSR 2008: 70m L x 12m W x 4.9m H	4116.00 cum			
<b>Item No.2:</b> Providing and fixing muli bamboo champa-kampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both sides) at 300mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification at page 135, item 21.9 of TSR 2008: 70m L x 2.8m W	196.00 sqm			
<b>Item No.3:</b> Clearing of jungle i/c uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth up to 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish up to a distance of 50m outside the periphery of the area cleared as CPWD specification (Page 7, item 2.14): 70m L x 1.8m W	126.00 sqm			
<b>Item No.4:</b> Pumping out water bodies like ponds, lakes as per CPWDF specification (Page 8, item 2.17): 12m L x 23m W x 1.5m H	414.00 cum			
<b>Item No.5:</b> Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30cm, 1.5m in width as well as 10 sqm on plan) i/c disposal of excavated earth lead up to 50m outside the periphery of the area and neatly dressed as per CPWD classification (page 5, item 2.1): 12m L x 23m W x 1.5m H	414.00 cum			

Contd....2

Total A (Items 1 to5)				
B. Add overheads for site accommodation, mobilization/demobilization of resources, labour camps with minimum amenities required as labour laws etc. .....% of A				
C. Add cost index.....% of A				
Grand total (A+B+C)				
Grand Total rounded off				

Quoted cost: Rs..... (Rupees.....  
.....) only

Date:.....

Signature with seal

List of enclosures:

1. Deposit-at-Call for Rs..... (Rupees ..... ) only  
No..... of .....(Bank), ..... Branch.
2. Copy of ITC, PTC, Labour registration
3. Copy of PWD/CPWD/MES/BSNL enlistment
4. ....

भाकृ अनुप - पूषप  
ICAR-RC-NEH

Name of work: **Digging of Pond and construction of bamboo made Retaining Wall [Pond No.7 (2)] at Cocotilla Farm**  
 Division: **Main Scheme**  
 Location: **ICAR Research Complex, Lembucherra**  
 Rate: **Tripura Schedule of Rates 2008 for Buildings**

<b>Item No. &amp; details of work to be executed</b>		<b>Rate</b>	<b>Amount</b>	
<b>Description</b>	<b>Quantity</b>		<b>In figure</b>	<b>In words</b>
<b>Item No.1:</b> Providing and fixing barak bamboo, 75mm to 100mm dia posts, runners struts, bracing collars etc. fixed with MS nails, complete as per specification at Page 136, item 21.19 of TSR 2008: 70m L x 12m W x 4.9m H	4116.00 cum			
<b>Item No.2:</b> Providing and fixing muli bamboo champa-kampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both sides) at 300mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification at page 135, item 21.9 of TSR 2008: 70m L x 2.8m W	196.00 sqm			
<b>Item No.3:</b> Clearing of jungle i/c uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth up to 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish up to a distance of 50m outside the periphery of the area cleared as CPWD specification (Page 7, item 2.14): 70m L x 1.8m W	126.00 sqm			
<b>Item No.4:</b> Pumping out water bodies like ponds, lakes as per CPWDF specification (Page 8, item 2.17): 12m L x 23m W x 1.5m H	414.00 cum			
<b>Item No.5:</b> Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30cm, 1.5m in width as well as 10 sqm on plan) i/c disposal of excavated earth lead up to 50m outside the periphery of the area and neatly dressed as per CPWD classification (page 5, item 2.1): 12m L x 23m W x 1.5m H	414.00 cum			

Contd....2

Total A (Items 1 to5)				
B. Add overheads for site accommodation, mobilization/demobilization of resources, labour camps with minimum amenities required as labour laws etc. .....% of A				
C. Add cost index.....% of A				
Grand total (A+B+C)				
Grand Total rounded off				

Quoted cost: Rs..... (Rupees.....  
.....) only

Date:.....

Signature with seal

List of enclosures:

1. Deposit-at-Call for Rs..... (Rupees .....) only  
No..... of .....(Bank), ..... Branch.
2. Copy of ITC, PTC, Labour registration
3. Copy of PWD/CPWD/MES/BSNL enlistment
4. ....

भाकृ अनुप - पूषप  
ICAR-RC-NEH



Name of work: **Digging of Pond and construction of bamboo made Retaining Wall [Pond No.7 (3)] at Cocotilla Farm**  
 Division: **Main Scheme**  
 Location: **ICAR Research Complex, Lembucherra**  
 Rate: **Tripura Schedule of Rates 2008 for Buildings**

<b>Item No. &amp; details of work to be executed</b>		<b>Rate</b>	<b>Amount</b>	
<b>Description</b>	<b>Quantity</b>		<b>In figure</b>	<b>In words</b>
<b>Item No.1:</b> Providing and fixing barak bamboo, 75mm to 100mm dia posts, runners struts, bracing collars etc. fixed with MS nails, complete as per specification at Page 136, item 21.19 of TSR 2008: 70m L x 12m W x 4.9m H	4116.00 cum			
<b>Item No.2:</b> Providing and fixing muli bamboo champa-kampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both sides) at 300mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification at page 135, item 21.9 of TSR 2008: 70m L x 2.8m W	196.00 sqm			
<b>Item No.3:</b> Clearing of jungle i/c uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth up to 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish up to a distance of 50m outside the periphery of the area cleared as CPWD specification (Page 7, item 2.14): 70m L x 1.8m W	126.00 sqm			
<b>Item No.4:</b> Pumping out water bodies like ponds, lakes as per CPWDF specification (Page 8, item 2.17): 12m L x 23m W x 1.5m H	414.00 cum			
<b>Item No.5:</b> Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30cm, 1.5m in width as well as 10 sqm on plan) i/c disposal of excavated earth lead up to 50m outside the periphery of the area and neatly dressed as per CPWD classification (page 5, item 2.1): 12m L x 23m W x 1.5m H	414.00 cum			

Contd....2

Total A (Items 1 to5)				
B. Add overheads for site accommodation, mobilization/demobilization of resources, labour camps with minimum amenities required as labour laws etc. .....% of A				
C. Add cost index.....% of A				
Grand total (A+B+C)				
Grand Total rounded off				

Quoted cost: Rs..... (Rupees.....  
.....) only

Date:.....

Signature with seal

List of enclosures:

1. Deposit-at-Call for Rs..... (Rupees ..... ) only  
No..... of .....(Bank), ..... Branch.
2. Copy of ITC, PTC, Labour registration
3. Copy of PWD/CPWD/MES/BSNL enlistment
4. ....

भाकृ अनुप - पूषप  
ICAR-RC-NEH

Name of work: **Digging of Pond and construction of bamboo made Retaining Wall [Pond No.7 (4)] at Cocotilla Farm**  
 Division: **Main Scheme**  
 Location: **ICAR Research Complex, Lembucherra**  
 Rate: **Tripura Schedule of Rates 2008 for Buildings**

<b>Item No. &amp; details of work to be executed</b>		<b>Rate</b>	<b>Amount</b>	
<b>Description</b>	<b>Quantity</b>		<b>In figure</b>	<b>In words</b>
<b>Item No.1:</b> Providing and fixing barak bamboo, 75mm to 100mm dia posts, runners struts, bracing collars etc. fixed with MS nails, complete as per specification at Page 136, item 21.19 of TSR 2008: 70m L x 12m W x 4.9m H	4116.00 cum			
<b>Item No.2:</b> Providing and fixing muli bamboo champa-kampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both sides) at 300mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification at page 135, item 21.9 of TSR 2008: 70m L x 2.8m W	196.00 sqm			
<b>Item No.3:</b> Clearing of jungle i/c uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth up to 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish up to a distance of 50m outside the periphery of the area cleared as CPWD specification (Page 7, item 2.14): 70m L x 1.8m W	126.00 sqm			
<b>Item No.4:</b> Pumping out water bodies like ponds, lakes as per CPWDF specification (Page 8, item 2.17): 12m L x 23m W x 1.5m H	414.00 cum			
<b>Item No.5:</b> Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30cm, 1.5m in width as well as 10 sqm on plan) i/c disposal of excavated earth lead up to 50m outside the periphery of the area and neatly dressed as per CPWD classification (page 5, item 2.1): 12m L x 23m W x 1.5m H	414.00 cum			

Contd....2

Total A (Items 1 to5)				
B. Add overheads for site accommodation, mobilization/demobilization of resources, labour camps with minimum amenities required as labour laws etc. .....% of A				
C. Add cost index.....% of A				
Grand total (A+B+C)				
Grand Total rounded off				

Quoted cost: Rs..... (Rupees.....  
.....) only

Date:.....

Signature with seal

List of enclosures:

1. Deposit-at-Call for Rs..... (Rupees ..... ) only  
No..... of .....(Bank), ..... Branch.
2. Copy of ITC, PTC, Labour registration
3. Copy of PWD/CPWD/MES/BSNL enlistment
4. ....

भाकृ अनुप - पूषप  
ICAR-RC-NEH

Name of work: **Digging of Pond and construction of bamboo made Retaining Wall [Pond No.7 (5)] at Cocotilla Farm**  
 Division: **Main Scheme**  
 Location: **ICAR Research Complex, Lembucherra**  
 Rate: **Tripura Schedule of Rates 2008 for Buildings**

<b>Item No. &amp; details of work to be executed</b>		<b>Rate</b>	<b>Amount</b>	
<b>Description</b>	<b>Quantity</b>		<b>In figure</b>	<b>In words</b>
<b>Item No.1:</b> Providing and fixing barak bamboo, 75mm to 100mm dia posts, runners struts, bracing collars etc. fixed with MS nails, complete as per specification at Page 136, item 21.19 of TSR 2008: 70m L x 12m W x 4.9m H	4116.00 cum			
<b>Item No.2:</b> Providing and fixing muli bamboo champa-kampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both sides) at 300mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification at page 135, item 21.9 of TSR 2008: 70m L x 2.8m W	196.00 sqm			
<b>Item No.3:</b> Clearing of jungle i/c uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth up to 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish up to a distance of 50m outside the periphery of the area cleared as CPWD specification (Page 7, item 2.14): 70m L x 1.8m W	126.00 sqm			
<b>Item No.4:</b> Pumping out water bodies like ponds, lakes as per CPWDF specification (Page 8, item 2.17): 12m L x 23m W x 1.5m H	414.00 cum			
<b>Item No.5:</b> Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30cm, 1.5m in width as well as 10 sqm on plan) i/c disposal of excavated earth lead up to 50m outside the periphery of the area and neatly dressed as per CPWD classification (page 5, item 2.1): 12m L x 23m W x 1.5m H	414.00 cum			

Contd....2

Total A (Items 1 to5)				
B. Add overheads for site accommodation, mobilization/demobilization of resources, labour camps with minimum amenities required as labour laws etc. .....% of A				
C. Add cost index.....% of A				
Grand total (A+B+C)				
Grand Total rounded off				

Quoted cost: Rs..... (Rupees.....  
.....) only

Date:.....

Signature with seal

List of enclosures:

1. Deposit-at-Call for Rs..... (Rupees ..... ) only  
No..... of .....(Bank), ..... Branch.
2. Copy of ITC, PTC, Labour registration
3. Copy of PWD/CPWD/MES/BSNL enlistment
4. ....

भाकृ अनुप - पूषप  
ICAR-RC-NEH

Name of work: **Digging of Pond and construction of bamboo made Retaining Wall [Pond No.7 (6)] at Cocotilla Farm**  
Division: **Main Scheme**  
Location: **ICAR Research Complex, Lembucherra**  
Rate: **Tripura Schedule of Rates 2008 for Buildings**

<b>Item No. &amp; details of work to be executed</b>		<b>Rate</b>	<b>Amount</b>	
<b>Description</b>	<b>Quantity</b>		<b>In figure</b>	<b>In words</b>
<b>Item No.1:</b> Providing and fixing barak bamboo, 75mm to 100mm dia posts, runners struts, bracing collars etc. fixed with MS nails, complete as per specification at Page 136, item 21.19 of TSR 2008: 70m L x 12m W x 4.9m H	4116.00 cum			
<b>Item No.2:</b> Providing and fixing muli bamboo champa-kampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both sides) at 300mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification at page 135, item 21.9 of TSR 2008: 70m L x 2.8m W	196.00 sqm			
<b>Item No.3:</b> Clearing of jungle i/c uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth up to 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish up to a distance of 50m outside the periphery of the area cleared as CPWD specification (Page 7, item 2.14): 70m L x 1.8m W	126.00 sqm			
<b>Item No.4:</b> Pumping out water bodies like ponds, lakes as per CPWDF specification (Page 8, item 2.17): 12m L x 23m W x 1.5m H	414.00 cum			
<b>Item No.5:</b> Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30cm, 1.5m in width as well as 10 sqm on plan) i/c disposal of excavated earth lead up to 50m outside the periphery of the area and neatly dressed as per CPWD classification (page 5, item 2.1): 12m L x 23m W x 1.5m H	414.00 cum			

Contd....2

<b>Item No.6:</b> PVC sheet, 400 micron thick (page material – 22, SI.No. 432) for making the bund water proof and avoid mixing of water of different ponds: 420m L x 4.9m H	2058.00 sqm			
Total A (Items 1 to5)				
B. Add overheads for site accommodation, mobilization/demobilization of resources, labour camps with minimum amenities required as labour laws etc.  .....% of A				
C. Add cost index.....% of A				
Grand total (A+B+C)				
Grand Total rounded off				

Quoted cost: Rs..... (Rupees.....  
.....) only

Date:.....

Signature with seal

List of enclosures:

1. Deposit-at-Call for Rs..... (Rupees .....) only  
No..... of .....(Bank), ..... Branch.
2. Copy of ITC, PTC, Labour registration
3. Copy of PWD/CPWD/MES/BSNL enlistment
4. ....