



**ICAR Research Complex for NEH Region**  
Tripura Centre, P.O. Lembucherra 799 210  
West Tripura.



No. RC/TC(C-4)/2011/MS/Pt./1294

December 14, 2011.

**NOTICE INVITING TENDER**

On behalf of ICAR, **SEALED** tenders for each of the following work are hereby invited from the contractors having valid registration / enlistment of State PWD / CPWD / BSNL / MES or any other authorized construction agency:

Sl. No.	Name of work	Estimated cost	Earnest money
1.	Digging of Pond and C/o bamboo made Retaining wall under FSR-1	2,78,566.00	Rs.5570/-
2.	Digging of Pond and C/o bamboo made Retaining Wall under FSR-2 (Phase-I)	2,19,362.00	Rs.4390/-
3.	Digging of Pond and C/o bamboo made Retaining Wall under FSR-2 (Phase-II)	3,99,283.00	Rs.7985/-
4.	Digging of Pond and C/o bamboo made Retaining Wall under FSR-3	3,43,708.00	Rs.6875/-
5.	Digging of Pond and C/o bamboo made Retaining Wall under FSR-3 (I)	78,140.00	Rs.1565/-

Detail Plan & Estimate-cum-Tender Paper will be available at our website <http://www.tripuraicar.gov.in>

Last date of receiving tenders: **29<sup>th</sup> December 2011 (up to 3 P.M.)**

Terms & Conditions

1. The received tenders (**separately for each of the above five works**) may be opened on the above date and time, if possible. The bidder himself or his authorized representative may remain present on the date of opening.
2. The successful bidder will have to undertake the awarded work within 7(seven) days of receipt of work order and to complete the same within a reasonable time of 30 (thirty) days or as may be specified in the work order.
3. The successful bidder has to adhere to the Plan & Estimate while minor deviation as may be specified by the undersigned/concerned Scientist I/c. will be allowed subject to approval of the undersigned and further subject to the condition that the total expenditure must remain restricted to the administrative approved costs for each of the above works.
1. On completion of the allotted work, the bill in triplicate with **Measurement Book** duly signed by the Tech. Officer (AAS) and copy of the handing over report may be submitted to the undersigned for arranging payment. The payment will be made from our Complex's H. Qrs., Umiam, Meghalaya against bidder's bills and other related documents.
2. The undersigned reserves the right to accept and / or reject any tender including the lowest one without assigning any reason thereof.
3. Tenders are to be incorporated with copies of Enlistment, Registration, Labour Registration and ITC, PTC etc.
4. Earnest money in the form of **Deposit-at-Call (No DD or Cheque)** in favour of the undersigned of any bank must be attached with the tenders.
5. The cover containing the tender must be superscripted by 'Tender for (name of work).

(M. DATTA)  
Joint Director

Copy to D. Daschadhuri for uploading to our website

**Phone No. 0381-2400047, 2865537, 2400883 (Office), 0381-2353725 (Res.-JD):**

**Tele Fax.0381-2865537, 2865201**

**Visit our website: <http://www.tripuraicar.gov.in>**

## DETAILS OF WORK- Farming System Research (FSR) – 1

Name of the work : Digging of Pond and construction of Bamboo Retaining wall  
Division : Division of Fisheries  
Office : ICAR Research Complex for NEH Region, Tripura Centre, Lembucherra

Item No	Works	Quantity	Quoted Rate (Rs)	Amount (Rs)
1	Providing and fixing barak bamboo 75 mm to 100 mm dia posts, runners, struts, bracing, collars etc fixed with MS nails complete as per specification	1881.60 m		
2	Providing and fixing muli bamboo champakampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both side) at 300 mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification	234.24 m		
3	Clearing of jungle including uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth upto 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish upto a distance of 50m outside the periphery of the area cleared as per CPWD specification	292.80 sqm		
4	Pumping out water from water bodies like ponds, lakes etc as per CPWD specification	830.72 cum		
5	Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30 cm, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth lead up to 50m outside the periphery of the area and lift upto 1.5m disposed earth to be leveled and neatly dressed as per CPWD classification	1661.45 cum		

Total Amount Quoted: Rs .....

## DETAILS OF WORK- Farming System Research (FSR) – 2 [Phase I]

Name of the work : Digging of Pond and construction of Bamboo Retaining wall  
Division : Division of Fisheries  
Office : ICAR Research Complex for NEH Region, Tripura Centre, Lembucherra

Item No	Works	Quantity	Quoted Rate (Rs)	Amount (Rs)
1	Providing and fixing barak bamboo 75 mm to 100 mm dia posts, runners, struts, bracing, collars etc fixed with MS nails complete as per specification	3634.40 m		
2	Providing and fixing muli bamboo champakampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both side) at 300 mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification	403.10 m		
3	Clearing of jungle including uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth upto 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish upto a distance of 50m outside the periphery of the area cleared as per CPWD specification	756.62 sqm		
4	Pumping out water from water bodies like ponds, lakes etc as per CPWD specification	2777.94 cum		

Total Amount Quoted: Rs .....

भाकृ अनुप - पूषप  
ICAR-RC-NEH

## DETAILS OF WORK- Farming System Research (FSR) – 2 [Phase II]

Name of the work : Digging of Pond and construction of Bamboo Retaining wall

Division : Division of Fisheries

Office : ICAR Research Complex for NEH Region, Tripura Centre, Lembucherra

Item No	Works	Quantity	Quoted Rate (Rs)	Amount (Rs)
1	Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30 cm, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth lead up to 50m outside the periphery of the area and lift upto 1.5m disposed earth to be leveled and neatly dressed as per CPWD classification	3703.92 cum		

Total Amount Quoted: Rs .....

भाकृ अनुप - पूषप  
ICAR-RC-NEH

Phone No. 0381-2400047, 2865537, 2400883 (Office), 0381-2353725 (Res.-JD):

Tele Fax.0381-2865537, 2865201

Visit our website: <http://www.tripuraicar.gov.in>

### DETAILS OF WORK- Farming System Research (FSR) – 3

Name of the work : Digging of Pond and construction of Bamboo Retaining wall

Division : Division of Fisheries

Office : ICAR Research Complex for NEH Region, Tripura Centre, Lembucherra

Item No	Works	Quantity	Quoted Rate (Rs)	Amount (Rs)
1	Providing and fixing barak bamboo 75 mm to 100 mm dia posts, runners, struts, bracing, collars etc fixed with MS nails complete as per specification	2371.60 m		
2	Providing and fixing muli bamboo champakampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both side) at 300 mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification	295.24 m		
3	Clearing of jungle including uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth upto 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish upto a distance of 50m outside the periphery of the area cleared as per CPWD specification	111.32 sqm		
4	Pumping out water from water bodies like ponds, lakes etc as per CPWD specification	1019.92 cum		
5	Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30 cm, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth lead up to 50m outside the periphery of the area and lift upto 1.5m disposed earth to be leveled and neatly dressed as per CPWD classification	2039.84 cum		

Total Amount Quoted: Rs .....

Phone No. 0381-2400047, 2865537, 2400883 (Office), 0381-2353725 (Res.-JD):

Tele Fax.0381-2865537, 2865201

Visit our website: <http://www.tripuraicar.gov.in>

## DETAILS OF WORK- Farming System Research (FSR) – 3 (I)

Name of the work : Digging of Pond and construction of Bamboo Retaining wall

Division : Division of Fisheries

Office : ICAR Research Complex for NEH Region, Tripura Centre, Lembucherra

Item No	Works	Quantity	Quoted Rate (Rs)	Amount (Rs)
1	Providing and fixing barak bamboo 75 mm to 100 mm dia posts, runners, struts, bracing, collars etc fixed with MS nails complete as per specification	1062.32 m		
2	Providing and fixing muli bamboo champakampa tarja (75mm wide) ceiling, strengthening with single split bamboo battens (both side) at 300 mm centre to centre and tied with GI wire 1.0mm complete (over required beams or fixed with a frame of suitable type) as per specification	82.93 m		
3	Clearing of jungle including uprooting wild vegetation, grass, bushes, shrubs, sapling and trees of girth upto 300mm measured at a height of 1.0m above ground level and removal and disposal of rubbish upto a distance of 50m outside the periphery of the area cleared as per CPWD specification	49.86 sqm		
4	Pumping out water from water bodies like ponds, lakes etc as per CPWD specification	223.99 cum		
5	Earth work in excavation in all kinds of soil over areas (exceeding average depth of 30 cm, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth lead up to 50m outside the periphery of the area and lift upto 1.5m disposed earth to be leveled and neatly dressed as per CPWD classification	335.99 cum		

Total Amount Quoted: Rs .....

Phone No. 0381-2400047, 2865537, 2400883 (Office), 0381-2353725 (Res.-JD):

Tele Fax.0381-2865537, 2865201

Visit our website: <http://www.tripuraicar.gov.in>