

TENDER PAPER FOR RTDIS TANKS UNDER NPCC PROJECT

Name of work: **Construction of 'Rain Tank Drip Irrigation System (RTDIS) under the NPCC Project.**

Division: Soil Science discipline of ICAR, Tripura Centre

Location: ICAR, Tripura Centre at Lembucherra.

Rate: Tripura Schedule of Rates 2008 for Building Works

Brief specification: Preparation of Water Tank with Aluminium Antenna for 2 (two) Units of such Tank for RTDIS.

Item No. & details of work to be executed		Rate	Amount	
Description	Quantity		In figure	In words
Item No.1: Earth Cutting	12 cum			
Item No.2: RCC work with 20mm nominal size of 1:2:4 (1 cement:2 fine sand:4 graded well burnt brick aggregate of 20mm nominal size).	10 cum			
Item No.3: Brick work (1:4)	10 cum			
Item No. 4: Steel work (TMT Bar) including centering and shuttering: 394.75+92.55+315.00 kg	803.30 Kg.			
Item No.5: 12mm Cement plastering	135 sqm			
Item No.6: Supply of Aluminium sheet Of 2.0 mm thick and preparation of Antenna	96.62 sqm			
Item No.7: Water proof cement paint	60 sqm			
Total for one Unit				
Grand Total for 3 units				

Quoted cost in words.....

.....) only

Signature of the Tenderer.....

Date

Seal

